

# Austin Regional Bank Structure

Structural Engineering Specification - Division 05 Metals  
Document SEER-AUS-STR-SPEC-042 | Revision 3 | Issued June 28, 2026

## 1. Purpose and scope

This specification establishes material, fabrication, delivery, erection, inspection, and documentation requirements for the reinforced structural steel framework at the Austin Regional Bank Structure. It governs the steel package associated with project AUS-BANK-01 and asset STR-AUS-STEEL-01.

The work includes wide-flange columns and beams, connection plates, high-strength bolts, shop primer, field touch-up, temporary bracing, and the records required to demonstrate conformance. The fabricator shall coordinate this specification with the approved structural drawings and the project schedule.

## 2. Applicable standards

Fabrication and erection shall comply with AISC 360 and the AISC Code of Standard Practice. Welding shall comply with AWS D1.1. High-strength bolting shall comply with the RCSC Specification. Material test reports shall reference the heat number marked on each primary member.

| Requirement              | Project criterion                              |
|--------------------------|------------------------------------------------|
| Structural steel         | ASTM A992, $F_y = 50$ ksi unless noted         |
| Plates                   | ASTM A572 Grade 50                             |
| High-strength bolts      | ASTM F3125 Grade A325                          |
| Fabricator certification | Current AISC Building Fabricator certification |
| Fire resistance          | 120-minute rated assemblies where scheduled    |

### 3. Fabrication and delivery controls

Atlas Structural Fabrication is the approved fabricator for the base steel package. Every shipping bundle shall identify purchase order PO-88142, project AUS-BANK-01, and asset STR-AUS-STEEL-01. The supplier shall transmit the bill of lading, packing list, material test reports, bolt lot certificates, and nonconformance status before the shipment leaves the fabrication facility.

#### 3.1 Austin structural framing requirements

The Austin structural frame uses ASTM A992 Grade 50 wide-flange members with ASTM A572 Grade 50 connection material. Column splices shall occur only at the elevations shown in the issued-for-construction drawings. Substitution of member grade, connection geometry, or bolt diameter requires written approval by the engineer of record.

Members shall be delivered in the erection sequence maintained in Primavera activity A44018. Shipping marks must remain legible after unloading. Field personnel shall isolate members with damaged flanges, illegible heat numbers, visible distortion, or coating contamination until disposition is documented.

#### 3.2 Receiving inspection

Receiving inspection shall verify quantities, shipping marks, heat numbers, visible condition, and accompanying mill certificates. Inspection record INS-55091 is the initial receiving record for the July steel delivery. Accepted material may be released to the laydown area after the inspector confirms that the source documentation is complete and traceable.

### 4. Bolted connections

Bolting crews shall maintain lot traceability for ASTM F3125 Grade A325 assemblies. Pre-installation verification and tensioning records shall be retained by connection location. Inspection record INS-55103 documents acceptance of the first bolt lot and the associated tensioning records.

## 5. Welding and corrective action

Weld procedure specifications and welder qualifications shall be available before field welding begins. Any weld discontinuity that exceeds AWS D1.1 acceptance criteria shall be recorded as a nonconformance, evaluated by the engineer of record, repaired using an approved procedure, and reinspected.

## 6. Documentation and retention

The contractor shall preserve the relationship between each physical member, supplier record, purchase order, schedule activity, inspection, and supporting document. Records shall include the source identifier and revision so that Seer can trace a project decision back to the original evidence.

| Record                    | Identifier               | Retention expectation                     |
|---------------------------|--------------------------|-------------------------------------------|
| Purchase order            | PO-88142                 | Project closeout plus 10 years            |
| Schedule milestone        | A44018                   | Project baseline and all approved updates |
| Receiving inspection      | INS-55091                | Project closeout plus 10 years            |
| Bolt inspection           | INS-55103                | Project closeout plus 10 years            |
| Engineering specification | SEER-AUS-STR-SPEC-042 R3 | Superseded revisions retained             |

End of specification